


ATLAS Endcap Signal Feedthrough Project

NSERC Review
TRIUMF, Jan 9th 2000

- **Overview of the Project**
- **Design**
- **Mechanical Components**
- **Electrical Components**
- **Assembly**
- **Quality Control**
- **Prototypes and Models**
- **Milestones and Schedule**
- **Budget and Management**
- **Conclusions**



Michel Lefebvre
University of Victoria
Physics and Astronomy


Overview of the Project

ATLAS liquid argon calorimetry has over 180k signal channels which must come through the cryostats.

Each feedthrough unit carries 1920 electrical channels.

Barrel: 64 feedthrough units


Endcap: 50 feedthrough units total



The endcap signal feedthrough project is an ATLAS **common fund** contribution from Canada

Part of the ATLAS Cryostat and Cryogenics Project (Leader: Pierre Pailier)


Production Readiness Review successfully passed at CERN on Jan 29th 1999



One endcap cryostat shown during assembly


Overview of the Project

Overall Design



Overview of the Project

Position of Units on Cryostat



Design

Design Considerations

The feedthrough design must satisfy many constraints:

- **gas and liquid pressure loads**
- **stresses caused by temperature gradients**
- **stresses caused by the cryostat thermal deformations**
- **welding** of the components must not damage the pin carriers
- **heat flow** through the units must be kept at an acceptable level
- the electrical properties must be adequate
- radiation environment

Specific to the endcap signal feedthroughs:

- **special cables required for HEC preamplifier power:**
 - special pigtailed
 - special vacuum cables
 - the **heat flow** for these special cables will be higher than for normal signal cables, but must nevertheless be kept at a reasonable level
- there are **4 different types of endcap feedthroughs**
 - 32 “Standard EM”
 - 8 “Special EM”
 - 8 “HEC (HEC and some EM)”
 - 2 “FCAL”

Design


Finite Element Analysis

Extensive FEA analysis of the feedthrough components and assembly has been performed and reviewed

e.g., Cold Flange Deflection
under 3.5 bar pressure load

```
ANSYS 5.3  
HUG 25 1998  
09:34:06  
MODAL SOLUTION  
STEP=1  
SUB =1  
TTMF=1  
UZ (AVG)  
RCYD=0  
PowerGraph.cs  
E-ACET-1  
AVRES=611  
IMX =.FH01-04  
SMN =-.101E-05  
SMX =.679E-04  
XV =-.733013  
YV =-.5  
ZV =-.75  
*DIST=.1422:1  
*X- -.060161  
*Y- =.008621  
*Z- =.006494  
A-LS= .121E-03  
Z-3JFFER  
EDGE  
101E-05  
.776E-05  
.150E-04  
.226E-04  
.301E-04  
.377E-04  
.452E-04  
.528E-04  
.604E-04  
.679E-04
```

maximum deflection of 68 microns




Mechanical Components

Pin Carriers and Flanges

A pin carrier is a low inclusion stainless steel matrix containing 7x64 or 8x64 electrical pins held in glass inserts

Pins and carrier gold plated


8-row pin carrier



Ambient flange with 4 pin carriers

4 pin carriers are welded on the ambient flange and the cold flange, all made of low inclusion SS




Bellows volume pumping hole



Mechanical Components

Bellows Assemblies

Bellows assemblies are designed to withstand up to the exceptional condition of 3.5 bar without squirming




↑ Bellows still axially stable, therefore not squirmed

← Both ends of the bellows were offset by 3mm to simulate the cryostat vessels offset

Mechanical Components

Cold Box or Funnel

- Mechanically connects the cold flange to the cold vessel, hence part of the pressure vessel
- Assymmetric design required because of space constraints
- FEA Designed to withstand the inter-vessel relative movements




To be cut here by an orbital cutter
before welding on bi-metallic junction
with cold vessel

CF Flange for tests

Electrical Components

Vacuum Cables



Carry the electrical channels from the ambient flange to the cold flange. Some carry calibration lines

Inaccessible after the bellows are welded to the flanges

Each vacuum cable must satisfy many demanding mechanical and electrical requirements

Successful R&D of vacuum cables in Canada with CRPP (E. Neuheimer- STC, M. Fincke-Keeler)


Over 100 cables produced and qualified

R&D critical in the evolution of the design and expertise.



Electrical Components

Pigtail Cables



Electrically connects the cold flange to the detector patch panel

Located in the cryostat cold vessel

Cannot be disconnected from a completed feedthrough

Developed by Orsay and Axon for all of ATLAS, along with other cables

6 different types of signal pigtails required in the endcap feedthrough

MOU signed between Orsay and ATLAS-Canada Dec 98

Orsay provides QA on cables



ATI connector

μ D connector or simple HEC connector

Electrical Components

Low Voltage Cables


Each endcap cryostat has 4 HEC feedthroughs which must supply the power for the HEC preamplifiers located in the LAr. This corresponds to a total of 40A in and out through each HEC feedthroughs

Low Voltage Vacuum Cables have been developed (M. Fincke-Keeler):

Carry the required currents without overheating

Allow minimum thermal path

Wire harness using 3 different wire gauges:




- AWG 24 - 900mA capacity
- AWG 26 - 550mA capacity
- AWG 28 - 400mA capacity

ATI connectors

Polyimide insulation for wires

$$T_{\max} \approx 40^{\circ} C$$


Detail thermal tests have been performed in Sep 99 in Victoria with HEC MPI personel




Heat leakage: 2.21W/cable
18.7 W/HEC feedthrough with 4 LV connections

Low Voltage Pigtails have also been developed (M. Fincke-Keeler)


Assembly Sequence



Assembly jig




**Cold flange
Cold box**




Pigtails

**Welding
(tacking) of
cold flange**




**Bellows
Ambient flange**

Vacuum cables




90° rotation



Final Welding


Assembly Assembly Jig




Rotation around two axes for assembly and welding

Assembly Welding

The cold box assembly is part of the pressure vessel
Negotiations with TIS completed Dec 99
Detailed Welding Plan produced
Qualification of welds and welders done by Feb 00



Quality Control Vacuum Test Station




Quality Control Cold Tests Station

Quality Plan includes full cold tests



**Prototype being inserted in the
cold vacuum test station**

Quality Control Temperature Cycling Apparatus



Controlled temperature cycling of pin carriers

Quality Control Electrical Test Stations

Quality Plan includes detailed electrical tests at various stages of assembly

before assembly welds

continuity

cold tests



continuity

cross talk

final electrical tests

precision resistance


cross talk



**Computer controlled
crosstalk measurement
apparatus**

UBC contribution

Quality Control Electrical Test Stations



**Computer controlled
precision resistance
measurement apparatus**



**Signal continuity and
wiring apparatus**

Prototypes and Models

Prototypes and Models have been crucial:

feedthrough design completion

parts selection

assembly jigs design and development

vacuum and electrical testing equipment and procedure

- **Unit model (1998)**
- **Prototype with dismountable flange**
- **Insertion model**
- **Pressure test vessel**
- **Full prototype (Jan 00)**



Milestones and Schedule

General

- **Production Readiness Review**
 - ◆ Passed in Jan 99
- **Leak Test Station and Electric Test Station**
 - ◆ Fully operational since Fall 98
- **Models and Prototypes**
 - ◆ Model done in 98
 - ◆ Prototype with dismountable flange done in 99
 - ◆ Insertion model done in Dec 99
 - ◆ TIS pressure test vessel done by Feb 00
 - ◆ Full prototype done in Jan 00
- **Welding**
 - ◆ Welding Plan completed in Dec 99
 - ◆ Agreement with TIS finalised in Dec 99
 - ◆ Qualification of welder done by Feb00
- **Production of Feedthrough Units**
 - ◆ First feedthrough unit done in May 00
 - ◆ Production of 25 units plus 3 spares by Jun 01
 - ◆ Shipment and testing at CERN: Jan 01 - Jun 01
 - ◆ Installation on cryostat : May 01 - Jul 01
 - ◆ Production of 25 units plus 3 spares by Apr 02
 - ◆ Shipment and testing at CERN: Nov 01 - Apr 01
 - ◆ Installation on cryostat : Mar 02 - May 02

Milestones and Schedule

Mechanical Components


- **Low Inclusion Steel (Timkin)**
 - ◆ P.O. out in Jul 99
 - ◆ Reception started in Oct 99 and resumed in Dec 99
- **Pin Carriers (Glasseal)**
 - ◆ P.O. out in Jun 99
 - ◆ Reception started in Oct 99
- **Cold and Ambient Flanges (EBCO)**
 - ◆ P.O. out in Nov 99
 - ◆ Reception in Mar 00
- **Funnel Parts and Bolts Rings (SICOM)**
 - ◆ P.O. out in Nov 99
 - ◆ Reception completed in Mar 00
- **Funnel Assemblies (Spec. Mech.)**
 - ◆ P.O. out in Jan 00
 - ◆ Reception to start in Apr 00
- **Seal and Cuff Rings for Bellows (SICOM)**
 - ◆ P.O. out in Nov 99
 - ◆ Reception completed in Feb 00
- **Bellows Assemblies (BOA)**
 - ◆ P.O. out in Jan 00
 - ◆ Reception to start in Apr 00
- **Other Components**
 - ◆ RF Gasket, Pipe fittings, Insulation, Pigtail restraint, Heaters
 - ◆ Reception to start in Jan 00

Milestones and Schedule

Electrical Components

- **Vacuum Cables**
 - ◆ RFQ reply from STC and FCI-Berg during fall 99
 - ◆ STC cables passed qualification
 - ◆ FCI-Berg cables qualification finalised Dec99 - Jan 00
 - ◆ Final contract to be awarded in Jan 00
 - ◆ Reception to start in Apr 00
- **Pigtail Cables (Axon via Orsay)**
 - ◆ MOU with Orsay signed in Dec 98
 - ◆ Reception at Orsay started in Nov 99
 - ◆ Reception in Victoria to start in Jan 00
- **Other Cables (Axon)**
 - ◆ RFQ reply received
 - ◆ P.O. out in Jan 00
- **Heaters**
 - ◆ Design finalised before Apr 00

Budget and Management Organizational Chart



Budget and Management

Budget Summary

PBS	WBS	Description	Sep 00	MIG COST PROFILE								MIG	Sep 00			contingency \$CAN
			00-01	97-98	98-99	99-00	00-01	01-02	02-03	03-04		spent	commit	uncommit		
			\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	%	%	%		
4	1	Endcap Signal Feedthroughs	\$455,694	\$224,375	\$261,707	\$503,577	\$1,594,824	\$1,174,668	\$192,783	\$28,793	\$3,980,726	36	50	14	\$432,753	
4.1	2	Project Setup	\$59,648	\$156,386	\$202,816	\$214,831	\$162,454	\$52,671	\$15,574	\$8,276	\$813,008	78	6	16	\$38,329	
4.1.1	3	Leak Test Setup	\$37,675	\$102,521	\$29,420	\$6,952	\$45,374	\$19,806	\$9,810	\$4,105	\$217,989	81	0	19	\$9,533	
4.1.2	3	Electric Test Setup	\$19,831	\$6,109	\$22,252	\$32,822	\$60,199	\$15,174	\$3,500	\$1,095	\$141,151	57	0	43	\$14,394	
4.1.3	3	Data Acquisition System	\$1,003	\$15,198	\$5,308	\$4,690	\$1,400	\$11,585	\$700	\$2,431	\$41,313	63	1	36	\$3,713	
4.1.4	3	FT Assembly Tools	\$0	\$0	\$10,135	\$591	\$44,724	\$840	\$211	\$0	\$56,500	19	76	5	\$7,144	
4.1.5	3	FT Prototypes	-\$2,636	\$32,558	\$135,094	\$163,028	\$4,057	\$101	\$0	\$218	\$335,055	98	2	0	\$1,077	
4.1.6	3	Misc Project Setup Items	\$3,775	\$0	\$607	\$6,748	\$6,700	\$5,165	\$1,353	\$427	\$21,000	53	0	47	\$2,467	
4.2	2	FT Series Assemblies	\$333,154	\$0	\$0	\$142,211	\$1,274,870	\$913,497	\$0	\$0	\$2,330,579	20	69	11	\$350,367	
4.2.1	3	Mechanical Components	\$120,328	\$0	\$0	\$141,714	\$421,821	\$490,111	\$0	\$0	\$1,053,647	25	63	12	\$129,310	
4.2.2	3	Electrical Components	\$212,153	\$0	\$0	\$399	\$832,049	\$362,483	\$0	\$0	\$1,194,932	18	77	5	\$203,318	
4.2.3	3	Shipping Crates	\$672	\$0	\$0	\$98	\$21,000	\$60,902	\$0	\$0	\$82,000	1	21	78	\$17,739	
4.3	2	Test Cryostat Signal FT	\$0	\$58,428	\$0	\$0	\$0	\$0	\$0	\$0	\$58,428	100	0	0	\$0	
4.4	2	Manpower	\$62,892	\$9,561	\$58,891	\$146,534	\$157,500	\$208,500	\$177,209	\$20,517	\$778,712	36	42	22	\$44,057	
4.4.1	3	Salaries and Benefits	\$57,253	\$9,561	\$55,092	\$129,328	\$131,000	\$185,000	\$156,268	\$11,799	\$678,048	37	48	15	\$26,341	
4.4.2	3	Consultation and Travel	\$2,505	\$0	\$1,016	\$17,206	\$19,500	\$18,500	\$18,225	\$8,718	\$83,164	25	4	71	\$14,821	
4.4.3	3	Other	\$3,134	\$0	\$2,784	\$0	\$7,000	\$5,000	\$2,716	\$0	\$17,500	34	0	66	\$2,896	

Contingencies total \$433k and are dominated by exchange rates:

+15% on 1.52 \$CAN/\$US (pin carriers and vacuum cables)


+25% on 0.200 \$CAN/FF (pigtailed)

+15% on 0.860 \$CAN/CHF (orbital cutter contribution)

The budget total net of contingencies is \$3.98M


36% of which has been spent (Sep 00)

50% of which has been committed (Sep 00)



Budget and Management


Budget Profile



	97-98	98-99	99-00	00-01	01-02	02-03	03-04	Total
Sep-00	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN
Budget	\$224,375	\$261,707	\$503,577	\$1,594,824	\$1,174,668	\$192,783	\$28,793	\$3,980,726
MIG spent	\$224,375	\$261,707	\$503,577	\$455,694	\$0	\$0	\$0	\$1,445,353
Proposed MIG Profile	\$249,000	\$650,000	\$1,226,880	\$960,000	\$700,000	\$170,000	\$24,846	\$3,980,726

Budget and Management

Integrated Budget Profile



	97-98	98-99	99-00	00-01	01-02	02-03	03-04	Total
Sep-00	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN
Budget	\$224,375	\$486,082	\$989,659	\$2,584,483	\$3,759,151	\$3,951,933	\$3,980,726	\$3,980,726
MIG spent	\$224,375	\$486,082	\$989,659	\$1,445,353	\$1,445,353	\$1,445,353	\$1,445,353	\$1,445,353
Proposed MIG Profile	\$249,000	\$899,000	\$2,125,880	\$3,085,880	\$3,785,880	\$3,955,880	\$3,980,726	\$3,980,726

Budget and Management

Series Assemblies Details

PBS	WBS	Description	MIG COST PROFILE								spent %	commit %	uncommit %	contingency \$CAN
			97-98 \$CAN	98-99 \$CAN	99-00 \$CAN	00-01 \$CAN	01-02 \$CAN	02-03 \$CAN	03-04 \$CAN	MIG \$CAN				
4	1	Endcap Signal Feedthroughs	\$224,375	\$261,707	\$503,577	\$1,594,824	\$1,174,668	\$192,783	\$28,793	\$3,980,726	36	50	14	\$432,753
4.1	2	Project Setup	\$156,386	\$202,816	\$214,831	\$162,454	\$52,671	\$15,574	\$8,276	\$813,008	78	6	16	\$38,329
4.2	2	FT Series Assemblies	\$0	\$0	\$142,211	\$1,274,870	\$913,497	\$0	\$0	\$2,330,579	20	69	11	\$350,367
4.2.1	3	Mechanical Components	\$0	\$0	\$141,714	\$421,821	\$490,111	\$0	\$0	\$1,053,647	25	63	12	\$129,310
4.2.1.0	4	Low Inclusion Steel	\$0	\$0	\$36,585	\$27,699	\$0	\$0	\$0	\$64,284	100	0	0	\$0
4.2.1.1	4	Pin Carriers	\$0	\$0	\$37,019	\$175,000	\$469,611	\$0	\$0	\$681,630	4	84	12	\$106,130
4.2.1.2	4	Warm Flanges	\$0	\$0	\$0	\$20,818	\$0	\$0	\$0	\$20,818	100	0	0	\$0
4.2.1.3	4	Cold Flanges	\$0	\$0	\$0	\$21,235	\$0	\$0	\$0	\$21,235	100	0	0	\$0
4.2.1.4	4	Bellow Assemblies	\$0	\$0	\$20,564	\$102,369	\$0	\$0	\$0	\$122,932	53	47	0	\$8,662
4.2.1.5	4	Bolt Flanges	\$0	\$0	\$18,370	\$0	\$0	\$0	\$0	\$18,370	100	0	0	\$0
4.2.1.6	4	Funnel Assemblies	\$0	\$0	\$12,813	\$52,160	\$0	\$0	\$0	\$64,973	42	58	0	\$3,773
4.2.1.7	4	Pipe Fittings	\$0	\$0	\$0	\$500	\$500	\$0	\$0	\$1,000	0	10	90	\$235
4.2.1.8	4	RF Gasket	\$0	\$0	\$0	\$1,200	\$0	\$0	\$0	\$1,200	0	0	100	\$300
4.2.1.9	4	Insulation	\$0	\$0	\$4,161	\$839	\$0	\$0	\$0	\$5,000	83	0	17	\$210
4.2.1.10	4	Welds	\$0	\$0	\$0	\$20,000	\$20,000	\$0	\$0	\$40,000	0	0	100	\$10,000
4.2.1.11	4	CF Flanges	\$0	\$0	\$12,203	\$0	\$0	\$0	\$0	\$12,203	100	0	0	\$0
4.2.2	3	Electrical Components	\$0	\$0	\$399	\$832,049	\$362,483	\$0	\$0	\$1,194,932	18	77	5	\$203,318
4.2.2.1	4	Pig Tail Cables	\$0	\$0	\$192	\$200,000	\$299,803	\$0	\$0	\$499,995	0	100	0	\$124,866
4.2.2.2	4	Vacuum Cables	\$0	\$0	\$0	\$510,576	\$0	\$0	\$0	\$510,576	33	67	0	\$51,500
4.2.2.3	4	Low Voltage Pigtail Cables	\$0	\$0	\$0	\$30,691	\$30,691	\$0	\$0	\$61,382	48	49	3	\$4,977
4.2.2.4	4	Low Voltage Vacuum Cables	\$0	\$0	\$0	\$19,490	\$19,490	\$0	\$0	\$38,980	5	90	5	\$5,750
4.2.2.5	4	Heaters	\$0	\$0	\$207	\$31,793	\$0	\$0	\$0	\$32,000	1	20	79	\$7,245
4.2.2.6	4	Extra HEC Pigtails	\$0	\$0	\$0	\$12,499	\$12,499	\$0	\$0	\$24,998	46	46	8	\$2,230
4.2.2.7	4	Temperature Probes	\$0	\$0	\$0	\$27,000	\$0	\$0	\$0	\$27,000	0	0	100	\$6,750
4.2.3	3	Shipping Crates	\$0	\$0	\$98	\$21,000	\$60,902	\$0	\$0	\$82,000	1	21	78	\$17,739
4.3	2	Test Cryostat Signal FT	\$58,428	\$0	\$0	\$0	\$0	\$0	\$0	\$58,428	100	0	0	\$0
4.4	2	Manpower	\$9,561	\$58,891	\$146,534	\$157,500	\$208,500	\$177,209	\$20,517	\$778,712	36	42	22	\$44,057
4.4.1	3	Salaries and Benefits	\$9,561	\$55,092	\$129,328	\$131,000	\$185,000	\$156,268	\$11,799	\$678,048	37	48	15	\$26,341
4.4.2	3	Consultation and Travel	\$0	\$1,016	\$17,206	\$19,500	\$18,500	\$18,225	\$8,718	\$83,164	25	4	71	\$14,821
4.4.3	3	Other	\$0	\$2,784	\$0	\$7,000	\$5,000	\$2,716	\$0	\$17,500	34	0	66	\$2,896

Budget and Management

Project Setup Details

PBS	WBS	Description	MIG COST PROFILE							MIG	spent %	commit %	uncommit %	contingency \$CAN
			97-98 \$CAN	98-99 \$CAN	99-00 \$CAN	00-01 \$CAN	01-02 \$CAN	02-03 \$CAN	03-04 \$CAN					
4	1	Endcap Signal Feedthroughs	\$224,375	\$261,707	\$503,577	\$1,594,824	\$1,174,668	\$192,783	\$28,793	\$3,980,726	36	50	14	\$432,753
4.1	2	Project Setup	\$156,386	\$202,816	\$214,831	\$162,454	\$52,671	\$15,574	\$8,276	\$813,008	78	6	16	\$38,329
4.1.1	3	Leak Test Setup	\$102,521	\$29,420	\$6,952	\$45,374	\$19,806	\$9,810	\$4,105	\$217,989	81	0	19	\$9,533
4.1.1.1	4	He Leak Tester	\$29,677	\$4,368	\$91	\$35,000	\$2,500	\$2,310	\$1,055	\$75,000	91	0	9	\$1,606
4.1.1.2	4	RGA	\$17,500	\$0	\$0	\$0	\$0	\$0	\$0	\$17,500	100	0	0	\$0
4.1.1.3	4	Calibrated He leaks	\$2,265	\$1,130	\$0	\$1,674	\$0	\$0	\$0	\$5,069	100	0	0	\$0
4.1.1.4	4	Cold Cathode / Pirani Gauges	\$6,500	\$0	\$5	\$0	\$0	\$0	\$0	\$6,505	100	0	0	\$0
4.1.1.5	4	Scroll Pump	\$0	\$8,219	\$0	\$0	\$8,219	\$0	\$0	\$16,438	50	0	50	\$1,233
4.1.1.6	4	Cryo Cooler	\$13,637	\$0	\$0	\$0	\$0	\$0	\$0	\$13,637	100	0	0	\$0
4.1.1.7	4	Ion Pump Parts	\$1,654	\$0	\$0	\$0	\$0	\$0	\$0	\$1,654	100	0	0	\$0
4.1.1.8	4	Temperature Probes	\$0	\$4,334	\$1,383	\$500	\$1,000	\$500	\$284	\$8,000	71	0	29	\$571
4.1.1.9	4	Valves	\$15,933	\$489	\$0	\$1,000	\$1,000	\$1,000	\$578	\$20,000	82	0	18	\$895
4.1.1.10	4	Vacuum Parts	\$6,891	\$555	\$3,109	\$3,000	\$3,000	\$3,000	\$445	\$20,000	57	0	43	\$2,133
4.1.1.11	4	Misc Hardware	\$1,215	\$8,403	\$346	\$2,000	\$2,000	\$1,000	\$36	\$15,000	67	0	33	\$1,223
4.1.1.12	4	Temperature Cycling Setup	\$1,581	\$571	\$162	\$200	\$87	\$0	\$0	\$2,600	89	0	11	\$72
4.1.1.13	4	Design Station	\$5,670	\$915	\$0	\$0	\$0	\$0	\$0	\$6,585	100	0	0	\$0
4.1.1.14	4	Liquid Nitrogen	\$0	\$436	\$1,857	\$2,000	\$2,000	\$2,000	\$1,707	\$10,000	28	0	72	\$1,801
4.1.2	3	Electric Test Setup	\$6,109	\$22,252	\$32,822	\$60,199	\$15,174	\$3,500	\$1,095	\$141,151	57	0	43	\$14,394
4.1.2.1	4	DC Test Setup	\$0	\$14,058	\$1,746	\$8,043	\$1,000	\$1,000	\$154	\$26,000	61	0	39	\$2,102
4.1.2.2	4	Transient Test Setup	\$263	\$7,778	\$12,509	\$13,500	\$12,174	\$1,500	\$580	\$48,304	68	0	32	\$3,646
4.1.2.3	4	Pig Tail Cables for tests	\$5,846	\$0	\$0	\$6,676	\$0	\$0	\$0	\$12,522	100	0	0	\$0
4.1.2.4	4	Misc Hardware	\$0	\$417	\$3,222	\$2,000	\$2,000	\$1,000	\$361	\$9,000	49	0	51	\$1,151
4.1.2.5	4	Pig Tail Loop Cables for Tests	\$0	\$0	\$15,325	\$0	\$0	\$0	\$0	\$15,325	100	0	0	\$0
4.1.2.6	4	Digital Scope	\$0	\$0	\$20	\$29,980	\$0	\$0	\$0	\$30,000	0	0	100	\$7,495
4.1.3	3	Data Acquisition System	\$15,198	\$5,308	\$4,690	\$1,400	\$11,585	\$700	\$2,431	\$41,313	63	1	36	\$3,713
4.1.3.1	4	NT Server PC	\$5,762	\$0	\$0	\$0	\$5,838	\$0	\$0	\$11,600	50	0	50	\$1,460
4.1.3.2	4	NT Client PC for DAQ	\$3,883	\$0	\$2,469	\$0	\$0	\$0	\$0	\$6,352	100	0	0	\$0
4.1.3.3	4	NT Licences	\$394	\$0	\$0	\$0	\$0	\$0	\$0	\$394	100	0	0	\$0
4.1.3.4	4	GPIB Interface	\$787	\$0	\$1,166	\$0	\$1,047	\$0	\$0	\$3,000	65	0	35	\$262
4.1.3.5	4	LabView Licenses	\$3,853	\$205	\$0	\$900	\$0	\$400	\$142	\$5,500	89	0	11	\$146
4.1.3.6	4	Colour Printer	\$489	\$0	\$0	\$0	\$0	\$0	\$0	\$489	100	0	0	\$0
4.1.3.7	4	Printer	\$0	\$0	\$0	\$0	\$300	\$0	\$0	\$300	0	0	100	\$75
4.1.3.8	4	Misc Hard/Software and Services	\$31	\$424	\$1,055	\$500	\$400	\$300	\$290	\$3,000	55	14	30	\$271
4.1.3.9	4	NT Client PC for Controls	\$0	\$4,679	\$0	\$0	\$0	\$0	\$0	\$4,679	100	0	0	\$0
4.1.3.10	4	CAMAC controller	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	0	0	100	\$0
4.1.3.11	4	NT Client PC for CERN	\$29,677	\$0	\$0	\$0	\$4,000	\$0	\$2,000	\$6,000	0	0	100	\$1,500
4.1.4	3	FT Assembly Tools	\$0	\$10,135	\$591	\$44,724	\$840	\$211	\$0	\$56,500	19	76	5	\$7,144
4.1.4.1	4	Assembly Jigs	\$0	\$2,234	\$226	\$1,000	\$540	\$0	\$0	\$4,000	62	0	38	\$385
4.1.4.2	4	Welding Station	\$0	\$7,900	\$289	\$300	\$300	\$211	\$0	\$9,000	91	0	9	\$203
4.1.4.3	4	Crane	\$0	\$0	\$76	\$424	\$0	\$0	\$0	\$500	15	0	85	\$106
4.1.4.4	4	Orbital Cutter	\$0	\$0	\$0	\$43,000	\$0	\$0	\$0	\$43,000	0	100	0	\$6,450
4.1.5	3	FT Prototypes	\$32,558	\$135,094	\$163,028	\$4,057	\$101	\$0	\$218	\$335,055	98	2	0	\$1,077
4.1.5.1	4	Model FT	\$2,289	\$775	\$0	\$0	\$0	\$0	\$0	\$3,064	100	0	0	\$0
4.1.5.2	4	Weld Test Flanges and Pin Carriers	\$11,815	\$4,297	\$8,650	\$909	\$0	\$0	\$217	\$25,889	98	0	2	\$143
4.1.5.3	4	Glass Pin Carriers	\$0	\$50,818	\$0	-\$2,147	\$0	\$0	\$0	\$48,671	100	0	0	\$0
4.1.5.4	4	Ceramic Pin Carriers	\$0	\$63,446	\$0	-\$2,147	\$0	\$0	\$0	\$61,299	100	0	0	\$0
4.1.5.5	4	Warm Flanges	\$0	\$2,497	\$221	\$0	\$0	\$0	\$0	\$2,718	100	0	0	\$0
4.1.5.6	4	Cold Flanges	\$0	\$2,304	\$246	\$0	\$0	\$0	\$0	\$2,550	100	0	0	\$0
4.1.5.7	4	Bellows Assemblies	\$0	\$3,654	\$10,540	\$5,510	\$0	\$0	\$0	\$19,704	72	28	0	\$826
4.1.5.8	4	Bolt Flanges	\$0	\$0	\$246	\$0	\$0	\$0	\$0	\$246	100	0	0	\$0
4.1.5.9	4	Funnel Assemblies	\$0	\$2,663	\$2,497	\$0	\$0	\$0	\$0	\$5,160	100	0	0	\$0
4.1.5.10	4	Vacuum Cables	\$18,453	\$0	\$120,470	\$359	\$0	\$0	\$0	\$139,282	100	0	0	\$0
4.1.5.11	4	Low Voltage Vacuum cables	\$0	\$4,086	\$0	\$0	\$0	\$0	\$0	\$4,086	100	0	0	\$0
4.1.5.12	4	Low Voltage Pigtails	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	100	0	0	\$0
4.1.5.13	4	Pipe Fittings	\$0	\$554	\$0	\$0	\$0	\$0	\$0	\$554	100	0	0	\$0
4.1.5.14	4	Pigtails	\$0	\$0	\$17,934	\$397	\$0	\$0	\$0	\$18,331	100	0	0	\$0
4.1.5.15	4	Insulation	\$0	\$0	\$2,225	\$1,175	\$101	\$0	\$0	\$3,500	73	24	3	\$108
4.1.6	3	Misc Project Setup Items	\$0	\$607	\$6,748	\$6,700	\$5,165	\$1,353	\$427	\$21,000	53	0	47	\$2,467
4.2	2	FT Series Assemblies	\$0	\$0	\$142,211	\$1,274,870	\$913,497	\$0	\$0	\$2,330,579	20	69	11	\$350,367
4.3	2	Test Cryostat Signal FT	\$58,428	\$0	\$0	\$0	\$0	\$0	\$0	\$58,428	100	0	0	\$0
4.3.1	3	Pin Carriers	\$56,960	\$0	\$0	\$0	\$0	\$0	\$0	\$56,960	100	0	0	\$0
4.3.4	3	Bolt Flanges	\$1,468	\$0	\$0	\$0	\$0	\$0	\$0	\$1,468	100	0	0	\$0
4.4	2	Manpower	\$9,561	\$58,891	\$146,534	\$157,500	\$208,500	\$177,209	\$20,517	\$778,712	36	42	22	\$44,057

Budget and Management Responsibilities

- **Design**
- **Fabrication**
 - ◆ **Signal Pigtails purchased from Orsay**
- **Commissioning**
- **Transport**
- **Reception**
 - ◆ **Electrical and ambient vacuum testing**
 - ◆ **Leak tester provided by ATLAS CERN**
- **Electrical tests after installation**
- **Assistance during installation**
 - ◆ **Up to SF50k towards the cost of an orbital cutter**
 - ◆ **Assistance during welding on the cryostat**
 - ◆ **Assistance for leak testing during/after installation**

- **Still under discussion**
 - ◆ **Who covers cost of T probes**
 - ◆ **Manpower to connect warm cables to ambient flange**

Conclusions

Endcap Signal Feedthrough Project

- **Crucial component of ATLAS LAr**
- **Complex and manpower intensive**
- **Production has started**
 - ◆ **First unit constructed in July 00**
 - ◆ **Proceeding cautiously with emphasis on QA/QC**
- **Extensive QC programme further developed**
- **All major purchase orders out**
- **All components (except pigtails, pin carriers and a few cables) likely to be in hand by the end of FY 00-01**
- **Production rate still in line with cryostat schedule**
 - ◆ **Pin carrier procurement on critical path**
 - ◆ **To be reassessed when pin carrier procurement reaches full rate**
- **Budget within the allocated MIG**
 - ◆ **Built-in contingencies**
 - ◆ **Purchase of FF for pigtails under investigation**
 - ◆ **Requires close monitoring**