



ATLAS Endcap Signal Feedthrough Project

NSERC Review
TRIUMF 
14th December 2001

- Overview
- Status
 - Procurement of Components
 - Feedthrough Production
 - Shipment to CERN
 - Reception Tests at CERN
- Schedule
- QA/QC
- Budget and Management
- Conclusions



Michel Lefebvre
University of Victoria
Physics and Astronomy

Overview

ATLAS liquid argon calorimetry has over 180k signal channels which must come through the walls of the cryostats

Each feedthrough unit carries 1920 electrical channels.

Barrel: 64 feedthrough units (+spares)

Endcap: 50 feedthrough units total (+5 spares)

The endcap signal feedthrough project is an ATLAS **common fund** contribution from Canada (CHF 3360k CORE)

Part of the ATLAS Cryostat and Cryogenics Project

Extensively reviewed

ATLAS reviews

Project Review, BNL, Jun 12-13 1997

Baseline Design review CERN, Oct 13th 1997

Production Readiness Review, CERN, Jan 29th 1999


Activity/Systems Status Overview, CERN, Feb 11-12 2001

NSERC reviews


TRIUMF, Jan 9 2000

TRIUMF, Oct 19 2000

TRIUMF, Dec 14 2001



Overview




Seal ring OD = 326.4 mm

Total height = 699.9 mm


Procurement of Components

pin carriers

- Production halted August 2000 due to low inclusion steel problems
- Production restarted February 2001.
All problems solved.
- HCC/GSP followed very closely, coordinated by Tom Muller at BNL
- UVic has received 270 units so far
- Delivery rate not an issue anymore
- BNL has received all the units required for the barrel feedthroughs: expect delivery rate to increase even further



pin carrier procurement
270/550 received



Procurement of Components

Other Mechanical Components

ambient flanges, cold flanges,
bellows assemblies (bellows, cuff
rings, seal rings), funnel
assemblies, heaters components,
rohacell, ambient flange glands

ALL IN STOCK



Procurement of Components

Electrical Components


Pigtails (7 types, require 750 for one endcap)

1273/1725(ordered) or 74% received

} We have all we need for the first endcap

Vacuum cables (2 types, require 750 for one endcap)

1790/1790(ordered) or 100% received



Feedthrough Production

At the University of Victoria

as of 03/12/2001

22 feedthrough units produced
of which 17 at CERN



vacuum cable installation



Shipment to CERN



crated feedthroughs




first 4 HEC feedthroughs in crate
(02/11/01)

Each feedthrough has its own crate

- they come in two sizes

4 feedthrough crates are then crated together for shipment

Reception Tests at CERN



Feedthrough units are tested upon reception at CERN:

- visual inspection
- leak test (ambient temperature)
- electrical test (cross-talk)



The electrical testing equipment will also be used on the cryostat after feedthrough installation

Schedule

Date	Build (total)	Type	At CERN
30-nov-2001	(13 STD, 4 SPCL, 4 HEC and 1 FCAL built to date)		
31-dec-2001	2 (24)	(2 STD)	21
31-jan-2002	4 (28)	(4 STD)	21
28-feb-2002	3 (31)	(1 HEC, 1 SPCL, 1 STD)	30 (ECC+)
31-mar-2002	3 (34)	(2 STD, 1 FCAL)	30
30-apr-2002	3 (37)	(2 HEC, 1 SPCL)	33
31-may-2002	3 (40)	(1 HEC, 2 SPCL)	35
30-jun-2002	4 (44)	(4 STD)	38
31-jul-2002	3 (47)	(3 STD)	42
31-aug-2002	2 (49)	(2 STD)	46
30-sep-2002	4 (53)	(4 STD)	46
15-oct-2002	2 (55)	(1 HEC, 1 SPCL)	50 (ECA)
15-nov-2002			55

7 months delay in the first endcap cryostat ECC delivery to CERN

6 months delay in the feedthrough production due to pin carrier procurement problems (now all solved)

- negligible impact on project cost: feedthrough installation on ECA at about the same date as planned in Oct 00
- used the delay to complete
 - reception tests on all material
 - the development of the QA/QC procedure and documents
 - the testing equipment for CERN

Oct 00 schedule:

ECC delivery to CERN
feedthrough installation

Jul 01
Sep 01 – Oct 01

Current Schedule:

ECC delivery to CERN
feedthrough installation
ECA delivery to CERN
feedthrough installation

11 Feb 02
15 Mar 02 – 30 Apr 02
31 Jul 02
Oct 02 ?

Endcap feedthrough production proceeding very well (40% produced)

Reception tests at CERN performing as planned

The project is not on the critical path

Schedule: reception and installation

Feedthrough reception at CERN started in October 2001

Reception tests fully commissioned

Two persons at CERN for reception tests

- 2.5 months in 2001
- foresee 2 times 1.5 months in 2002

Two persons at CERN for assistance during installation

- foresee 2 times 1.5 months in 2002 (very likely to overlap with one or both reception test periods)
- foresee 2 times 2 months for warm cable installation and final electrical tests



More than half of the barrel feedthroughs (BNL) installed on the barrel cryostat.

Expect an average of about one unit installed per day for the endcap

Quality Assurance / Quality Control

QA/QC is critical to the success of the project

Very detailed document released (QA/QC version 4, Mar 01)

- updated version to be released in Jan 02
- procedures and documents have been updated after the experience gained from building the first feedthroughs

All TIS (CERN Safety) concerns have been addressed (Dec 00)

All information stored in a purpose-built database

- material traceability
- production and reception test results
- available on the web:

<http://particle.phys.uvic.ca/~web-atlas/atlas/feedthroughs/status/>

Quality Assurance / Quality Control

production status summary



[Return to ATLAS Endcap Signal Feedthroughs](#)

EndCap Signal FeedThrough Production Status

ser #	type	started	completed	shipped	reception tests	officially received	installed
ft00	Standard	6 Jul 00	13 Oct 00	28 Sep 01	23 Oct 01	-	-
ft01	Standard	27 Sep 00	11 Sep 01	28 Sep 01	25 Oct 01	-	-
ft02	Standard	11 Oct 00	15 Dec 00	28 Sep 01	27 Oct 01	-	-
ft03	Standard	27 Mar 01	20 Apr 01	28 Sep 01	29 Oct 01	-	-
ft04	Standard	25 Apr 01	10 May 01	16 Oct 01	12 Nov 01	-	-
ft05	Standard	7 May 01	24 May 01	16 Oct 01	8 Nov 01	-	-
ft06	Standard	23 May 01	5 Jun 01	16 Oct 01	8 Nov 01	-	-


Quality Assurance / Quality Control

cross talk measurements at UVic and at CERN



Quality Assurance / Quality Control

resistance measurements at UVic



Budget and Management

Responsibilities


- Design
- Fabrication
 - ◆ Signal Pigtails purchased from Orsay
- Commissioning
- Transport
- Reception
 - ◆ Electrical and ambient vacuum testing
 - ◆ Leak tester provided by ATLAS CERN
- Electrical tests after installation
- Assistance during installation
 - ◆ Up to SF50k towards the cost of an orbital welder
 - ◆ Assistance during welding on the cryostat
 - ◆ Assistance for leak testing during/after installation
 - ◆ Manpower to connect warm cables to ambient flange

Budget and Management


Budget Status

MIG amount: \$4.280M
Current budget: \$4.091M (net of contingencies)
Contingencies: \$0.213M

Endcap Signal Feedthrough Project



Endcap Signal Feedthrough Project including contingencies



Budget and Management


Budget Summary

PBS	WBS	Description	MIG COST PROFILE									Dec 01			
			01-02	97-98	98-99	99-00	00-01	01-02	02-03	03-04	MIG	spent	commit	uncommit	contingency
			\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	%	%	%
4	1	Endcap Signal Feedthroughs	\$557,615	\$224,375	\$266,888	\$523,358	\$1,233,264	\$1,302,151	\$422,943	\$118,502	\$4,091,482	69	26	5	\$212,829
4.1	2	Project Setup	\$33,604	\$156,386	\$207,997	\$209,536	\$87,019	\$41,418	\$79,657	\$8,149	\$790,163	88	6	6	\$18,183
4.1.1	3	Leak Test Setup	\$10,200	\$102,521	\$29,420	\$6,838	\$39,994	\$16,105	\$18,621	\$4,111	\$217,611	87	0	13	\$6,337
4.1.2	3	Electric Test Setup	\$11,718	\$6,109	\$22,252	\$32,803	\$35,767	\$13,371	\$1,071	\$764	\$112,138	97	0	3	\$872
4.1.3	3	Data Acquisition System	\$5,749	\$15,198	\$5,308	\$4,690	\$5,550	\$6,592	\$2,000	\$816	\$40,154	91	0	9	\$915
4.1.4	3	FT Assembly Tools	\$0	\$0	\$10,135	\$591	\$0	\$0	\$49,811	\$0	\$60,536	18	81	1	\$7,553
4.1.5	3	FT Prototypes	\$0	\$32,558	\$140,275	\$157,847	-\$956	\$0	\$0	\$0	\$329,724	100	0	0	\$0
4.1.6	3	Misc Project Setup Items	\$5,938	\$0	\$607	\$6,768	\$6,663	\$5,350	\$8,154	\$2,458	\$30,000	67	0	33	\$2,506
4.2	2	FT Series Assemblies	\$382,335	\$0	\$0	\$167,287	\$974,803	\$1,019,389	\$118,174	\$15,016	\$2,294,670	66	31	2	\$154,830
4.2.1	3	Mechanical Components	\$289,985	\$0	\$0	\$166,791	\$203,563	\$633,651	\$20,000	\$0	\$1,024,005	64	35	0	\$53,186
4.2.2	3	Electrical Components	\$84,935	\$0	\$0	\$399	\$758,353	\$365,738	\$76,174	\$0	\$1,200,664	70	30	0	\$89,244
4.2.3	3	Shipping Crates	\$7,416	\$0	\$0	\$98	\$12,886	\$20,000	\$22,000	\$15,016	\$70,000	29	0	71	\$12,400
4.3	2	Test Cryostat Signal FT	\$0	\$58,428	\$0	\$0	\$0	\$0	\$0	\$0	\$58,428	100	0	0	\$0
4.4	2	Manpower	\$141,675	\$9,561	\$58,891	\$146,534	\$171,442	\$241,344	\$225,112	\$95,337	\$948,222	56	32	13	\$39,816
4.4.1	3	Salaries and Benefits	\$125,191	\$9,561	\$55,092	\$129,328	\$142,873	\$193,844	\$159,692	\$76,288	\$766,678	60	37	3	\$15,232
4.4.2	3	Consultation and Travel	\$16,484	\$0	\$1,016	\$17,206	\$20,368	\$47,500	\$61,455	\$19,049	\$166,594	33	10	57	\$23,593
4.4.3	3	Other	\$0	\$0	\$2,784	\$0	\$8,201	\$0	\$3,965	\$0	\$14,950	73	0	27	\$991

Contingencies total \$213k and are dominated by exchange rates:

- +15% on 1.65 \$CAN/\$US (pin carriers)
- +25% on 0.230 \$CAN/FF (pigtailed)
- +15% on 0.980 \$CAN/CHF (orbital welder contribution)

Endcap Signal Feedthrough Project including contingencies




The budget total net of contingencies is \$4.09M

69% of which has been spent (Dec 01)

26% of which has been committed (Dec 01)

Budget and Management


Budget Profile



	97-98	98-99	99-00	00-01	01-02	02-03	03-04	Total
Dec 01	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN
Budget	\$224,375	\$266,888	\$523,358	\$1,233,264	\$1,302,151	\$422,943	\$118,502	\$4,091,482
MIG spent (UVic and TRIUMF)	\$224,375	\$266,888	\$523,358	\$1,233,264	\$557,615	\$0	\$0	\$2,805,501
Proposed MIG Profile	\$249,000	\$584,000	\$1,292,880	\$960,000	\$450,000	\$450,000	\$105,602	\$4,091,482

Budget and Management

Integrated Budget Profile



	97-98	98-99	99-00	00-01	01-02	02-03	03-04	Total
Dec 01	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN
Budget	\$224,375	\$491,263	\$1,014,621	\$2,247,886	\$3,550,037	\$3,972,980	\$4,091,482	\$4,091,482
MIG spent (UVic and TRIUMF)	\$224,375	\$491,263	\$1,014,621	\$2,247,886	\$2,805,501	\$2,805,501	\$2,805,501	\$2,805,501
Proposed MIG Profile	\$249,000	\$833,000	\$2,125,880	\$3,085,880	\$3,535,880	\$3,985,880	\$4,091,482	\$4,091,482

Budget and Management

Series Assemblies Details

PBS	WBS	Description	MIG COST PROFILE							MIG	spent %	co commit %	unco mmit %	contingency \$CAN
			97-98	98-99	99-00	00-01	01-02	02-03	03-04					
			\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN	\$CAN					
4	1	Endcap Signal Feedthroughs	\$224,375	\$266,888	\$523,358	\$1,233,264	\$1,302,151	\$422,943	\$118,502	\$4,091,482	69	26	5	\$212,829
4.1	2	Project Setup	\$156,386	\$207,997	\$209,536	\$87,019	\$41,418	\$79,657	\$8,149	\$790,163	88	6	6	\$18,183
4.2	2	FT Series Assemblies	\$0	\$0	\$167,287	\$974,803	\$1,019,389	\$118,174	\$15,016	\$2,294,670	66	31	2	\$154,830
4.2.1	3	Mechanical Components	\$0	\$0	\$166,791	\$203,563	\$633,651	\$20,000	\$0	\$1,024,005	64	35	0	\$53,186
4.2.1.0	4	Low Inclusion Steel	\$0	\$0	\$61,853	\$2,431	\$0	\$0	\$0	\$64,284	100	0	0	\$0
4.2.1.1	4	Pin Carriers	\$0	\$0	\$36,827	\$49,719	\$612,797	\$0	\$0	\$699,344	52	48	0	\$50,101
4.2.1.2	4	Warm Flanges	\$0	\$0	\$0	\$20,818	\$0	\$0	\$0	\$20,818	100	0	0	\$0
4.2.1.3	4	Cold Flanges	\$0	\$0	\$0	\$21,235	\$0	\$0	\$0	\$21,235	100	0	0	\$0
4.2.1.4	4	Bellow Assemblies	\$0	\$0	\$20,564	\$59,726	\$0	\$0	\$0	\$80,290	100	0	0	\$0
4.2.1.5	4	Bolt Flanges	\$0	\$0	\$18,370	\$0	\$0	\$0	\$0	\$18,370	100	0	0	\$0
4.2.1.6	4	Funnel Assemblies	\$0	\$0	\$12,813	\$47,315	\$0	\$0	\$0	\$60,128	100	0	0	\$0
4.2.1.7	4	Pipe Fittings	\$0	\$0	\$0	\$172	\$0	\$0	\$0	\$172	100	0	0	\$0
4.2.1.8	4	RF Gaskets and O'Rings	\$0	\$0	\$0	\$2,146	\$854	\$0	\$0	\$3,000	74	0	26	\$199
4.2.1.9	4	Insulation	\$0	\$0	\$4,161	\$0	\$0	\$0	\$0	\$4,161	100	0	0	\$0
4.2.1.10	4	Welds	\$0	\$0	\$0	\$0	\$20,000	\$20,000	\$0	\$40,000	28	72	0	\$2,887
4.2.1.11	4	CF Flanges	\$0	\$0	\$12,203	\$0	\$0	\$0	\$0	\$12,203	100	0	0	\$0
4.2.2	3	Electrical Components	\$0	\$0	\$399	\$758,353	\$365,738	\$76,174	\$0	\$1,200,664	70	30	0	\$89,244
4.2.2.1	4	Pig Tail Cables	\$0	\$0	\$192	\$192,216	\$280,000	\$76,174	\$0	\$548,582	35	65	0	\$88,851
4.2.2.2	4	Vacuum Cables	\$0	\$0	\$0	\$471,810	\$39,290	\$0	\$0	\$511,100	100	0	0	\$0
4.2.2.3	4	Low Voltage Pigtail Cables	\$0	\$0	\$0	\$29,536	\$30,954	\$0	\$0	\$60,491	100	0	0	\$0
4.2.2.4	4	Low Voltage Vacuum Cables	\$0	\$0	\$0	\$38,056	\$449	\$0	\$0	\$38,505	100	0	0	\$0
4.2.2.5	4	Heaters	\$0	\$0	\$207	\$6,688	\$3,105	\$0	\$0	\$10,000	84	0	16	\$393
4.2.2.6	4	Extra HEC Pigtails	\$0	\$0	\$0	\$10,821	\$11,940	\$0	\$0	\$22,761	100	0	0	\$0
4.2.2.7	4	Temperature Probes	\$0	\$0	\$0	\$9,225	\$0	\$0	\$0	\$9,225	100	0	0	\$0
4.2.3	3	Shipping Crates	\$0	\$0	\$98	\$12,886	\$20,000	\$22,000	\$15,016	\$70,000	29	0	71	\$12,400
4.3	2	Test Cryostat Signal FT	\$58,428	\$0	\$0	\$0	\$0	\$0	\$0	\$58,428	100	0	0	\$0
4.4	2	Manpower	\$9,561	\$58,891	\$146,534	\$171,442	\$241,344	\$225,112	\$95,337	\$948,222	56	32	13	\$39,816
4.4.1	3	Salaries and Benefits	\$9,561	\$55,092	\$129,328	\$142,873	\$193,844	\$159,692	\$76,288	\$766,678	60	37	3	\$15,232
4.4.2	3	Consultation and Travel	\$0	\$1,016	\$17,206	\$20,368	\$47,500	\$61,455	\$19,049	\$166,594	33	10	57	\$23,593
4.4.3	3	Other	\$0	\$2,784	\$0	\$8,201	\$0	\$3,965	\$0	\$14,950	73	0	27	\$991

Conclusions

ATLAS Endcap Signal Feedthrough Project

- Crucial component of ATLAS Liquid Argon Calorimetry
- Complex and manpower intensive
 - ◆ UVic and TRIUMF personnel
- Production is 40% done
 - ◆ 22 units built and tested, 17 units at CERN, 4 in transit (as of 3 Dec 01)
 - ◆ Reception tests at CERN have started
 - ◆ Proceeding cautiously with emphasis on QA/QC
- Extensive QA/QC programme
- All components (except pin carriers and pigtailed) are in hand
- Pin carrier production and delivery not a problem anymore
- Production rate in line with cryostat schedule
 - ◆ Installation on ECC is scheduled for late March 2002
- Budget within the allocated MIG
 - ◆ Built-in contingencies
 - ◆ 95% of baseline costs either spent or committed