

ATLAS Liquid Argon Calorimeter Signal Feedthroughs


ATLAS Liquid Argon Calorimeter Workshop
Schloß Ringberg
September 27-30 1998

- Brief Overview
- Prototypes
- Vacuum Cable Development
- Test Station
- Endcap Specific Issues
- Management



Presented by Michel Lefebvre
University of Victoria
British Columbia, Canada

Endcap Cryostat (transverse view)



Signal Feedthroughs




Over 180k signal channels in the LAr calorimetry

High density and reliability required:

1920 pins per feedthrough unit

barrel: 64 units

endcaps: 50 units total



Design Issues

The design of the feedthrough components must satisfy many constraints:


- gas and liquid pressure loads;
- stresses caused by temperature gradients;
- stresses caused by the cryostat deformations between warm and cold;
- the welding of the components together must not damage the pin carriers;
- the heat flow through the units must be kept at an acceptable level;
- the electrical properties must be adequate;
- radiation environment;

Specific to the endcap signal feedthroughs:

- special cables are needed for the low voltage for the HEC preamplifier:
 - special pigtails;
 - special vacuum cables;
 - special warm cables (not part of feedthrough project)
 - the heat flow for these special cables will be higher than for normal signal cables, but must nevertheless be kept at a reasonable level.
- there are 4 different types of endcap feedthroughs
 - 32 Standard EM
 - 8 Special EM
 - 8 HEC (HEC and some EM)
 - 2 FCAL


Radiation Environment

(1 MeV $n_{eq}/cm^2/yr$)




- Up to 10^{16} $n/cm^2/yr$ and 2×10^6 Gy/y in the **FCAL**
- Less than 10^{12} $n/cm^2/yr$ and 20 Gy/y at the **EM electronics location**
- Less than 5×10^{12} $n/cm^2/yr$ and 50 Gy/y at the **Hadronic Endcap electronics location**

Dose (Gy/yr)




Pin Carrier Design



Finite Element Analysis of Feedthroughs

Ambient Flange unit


```
ANSYS 5.3  
JUL 16 1998  
10:14:59  
ELEMENTS  
PowerGraphics  
EFACET=1  
  
XV = -.891007  
YV = -.226995  
ZV = -.393167  
*DIST = .196612  
*XF = .061195  
*YF = -.010629  
*ZF = .075038  
A-ZS=62.778  
Z-BUFFER  
EDGE
```



Finite Element Analysis of Feedthroughs

Cold Flange Deflection under 3.5 bar pressure load

```
ANSYS 5.3
AUG 25 1998
09:34:06
NODAL SOLUTION
STEP=1
SUB =1
TIME=1
UZ (AVG)
RSYS=0
PowerGraphics
EFACET=1
AVRES=ALL
DMX =.680E-04
SMN =-.101E-06
SMX =.679E-04
XV =-.433013
YV =-.5
ZV =-.75
*DIST=.142211
*XF =.068161
*YF =.008621
*ZF =.006494
A-ZS=-.121E-05
Z-BUFFER
EDGE
-.101E-06
.746E-05
.150E-04
.226E-04
.301E-04
.377E-04
.452E-04
.528E-04
.604E-04
.679E-04
```




Finite Element Analysis of Feedthroughs

Cold Flange (Von Mises) Stress
under 3.5 bar pressure load,
seen from the LAr side

```
ANSYS 5.3  
AUG 24 1998  
16:49:00  
NODAL SOLUTION  
STEP=1  
SUB =1  
TIME=1  
SEQV (AVG)  
PowerGraphics  
EFACET=1  
AVRES=ALL  
DMX =.680E-04  
SMN =.101E+07  
SMX =.115E+09  
XV =-.433013  
YV =-.5  
ZV =-.75  
*DIST=.142211  
*XF =.068161  
*YF =.008621  
*ZF =.006494  
A-ZS=-.121E-05  
Z-BUFFER  
EDGE  
.101E+07  
.137E+08  
.264E+08  
.391E+08  
.518E+08  
.645E+08  
.772E+08  
.899E+08  
.103E+09  
.115E+09
```


maximum (Von Mises) stress of 115MPa
localized in the corner of the weld region
of the pin carrier



Yield and ultimate stress value for the flange and pin carrier material (AISI 304L stainless steel) are about 230MPa and 483MPa respectively

Finite Element Analysis of Feedthroughs


FEA model of the Funnel and bi-metallic joint. Simulated forces: 5387N for 3.5 bar internal pressure and 695N lateral force for the cryostats relative movements (barrel only)



Finite Element Analysis of Feedthroughs

Resulting Funnel (Von Mises) Stress

ANSYS 5.3
JUN 9 1997
12:51:04
NODAL SOLUTION
STEP=1
SUB =1
TIME=1
SEQV (AVG)
DMX =.332E-03
SMN =555995
SMX =.114E+09
SMXB=.195E+09
555995
132E+08
258E+08
384E+08
510E+08
637E+08
763E+08
889E+08
102E+09
114E+09



Pin Carrier Order for Prototypes

- BNL and Victoria plan to produce 2 or 3 feedthrough units each
- Total Order:
 - Glasseal
 - 20 pin carriers BNL
 - 20 pin carriers Victoria
 - These will be gold-plated
 - Pacific Coast Technologies
 - 10 pin carriers BNL
 - 10 pin carriers Victoria
 - These will NOT be gold-plated
- Costs
 - Glasseal
 - 448 pins: US\$ 1455 each for 20 + US\$ 40 for Au
 - 512 pins: US\$ 1621 each for 20 + US\$ 47 for Au
 - 448 pins: US\$ 593 each for 500
 - 512 pins: US\$ 659 each for 500
 - PCT
 - 448 pins: US\$ 3872 each for 10 + US\$ 1400 for Au
 - 512 pins: US\$ 3961 each for 10 + US\$ 1400 for Au
 - 448 pins: US\$ 1997 each for 500 + US\$ 200 for Au
 - 512 pins: US\$ 2027 each for 500 + US\$ 200 for Au

Other Mechanical Components for Prototypes

- All flanges expected late September
- 3 bellows expected 27th September
- funnel assemblies ordered, expected early October

Pin Carrier Technology Choice


- One of the most important goal of the prototyping work is to gather sufficient evidence for a [pin carrier technology choice](#);
- A [series of tests](#) have been devised, including
 - visual inspection;
 - ambient leak testing;
 - controlled temperature cycling, and leak tests;
 - welding of pin carriers in flanges, and leak tests;
 - complete feedthrough assembly, and leak tests;
 - severe tests on a few pin carriers;
 - high pressure;
 - rapid and/or repeated temperature cycling

Vacuum Cable Development in Canada


Signal Cables

- All-Flex design
 - cables made up of 2 flexible microstrip lines
 - rigid part of the connector are assembled around the two strip lines
- Aim at simpler and cheaper design
- Design work:
 - E. Neuheimer (CRPP Carleton)
 - G. Hoepfel (Strataflex, Toronto)
- Connector design retained:
 - plated-through plastic spacers (Strataflex proposition)
- 20 Prototypes in hand
 - one to BNL and one to Orsay for comments
 - one was recently irradiated in Grenoble (thanks to J. Collot)
 - Many thanks to Don Makowiecki for assistance
- Work towards pre-production (100) order ongoing
- Desired schedule:
 - soon Get comments from BNL and Orsay
 - 11/98 Place pre-production order
 - 02/98 Test on pre-production cables
 - 03/99 Place production order
 - 05/99 First delivery for ECC (aggressive...)
 - 11/00 First delivery for ECA
- Comments:
 - We anticipate dates of last deliveries to be non critical



Vacuum Cable Development in Canada




Vacuum Cable Development in Canada



Vacuum Cable Development in Canada




Leak Test Setup in Victoria



- Leak detection using He leak detector supported by an RGA
- Leak detector services warm and cold test stations
- Cooling by cryo-cooler or LN₂
- All assembled, in use

Leak Test Setup in Victoria



RGA

Ion Pump

Cold Tests


Ambient Test Platter

He Leak Tester


Leak Test Setup in Victoria



Leak Test Setup in Victoria



Leak Test Setup in Victoria





**Ambient Test
Platter Base**

RGA


He Leak Tester

Turbo Pump

Leak Test Setup in Victoria



Leak Test Setup in Victoria




**Controlled Temperature Cycling
Refrigerator for pin carriers**

All assembled


Capacity of 12 pin carriers

Cooled by Cryocooler or LN₂

Leak Test Setup in Victoria



Assembly Jig in Victoria



- Rotation about horizontal and vertical axis possible
- Various assembly scenarios under study
- Being assembled

Endcap Signal Feedthrough Project

Canadian Responsibilities

- Design
- Fabrication
 - Signal Pigtails purchased from Orsay
 - Low Voltage Pigtails purchased from MPI
- Commissioning
- Transport
- Assistance during installation:
 - Considering to cover the cost of an orbital cutter
 - Assistance during welding on the cryostat
 - Assistance for leak testing during installation
 - DC Electrical tests during the installation

Endcap Signal Feedthrough Team

Paul Birney	Senior Technologist, TRIUMF Leak test station Assembly tooling
Margret Fincke	Research Associate, Victoria Electric test station Vacuum cable development
Terry Hodges	Chief Engineer, TRIUMF Feedthrough unit design Finite element analysis
Aaron Dowling	Junior Technologist, Victoria
Richard Keeler	Faculty, Victoria Test stations Vacuum cable development
Roy Langstaff	Senior Draftsman, TRIUMF Feedthrough unit design Procurement issues
Michel Lefebvre	Faculty, Victoria Project leader
Mark Lenckowski	Draftsman, TRIUMF
Ernie Neuheimer	Research Scientist, CRPP Carleton Vacuum cable development
Paul Poffenberger	Production Manager, Victoria Leak test station Vacuum system
Greg Vowles	Junior Technologist, Victoria
On a consultant basis:	
Randy Sobie	Faculty, Victoria DAQ

Endcap Signal Feedthrough Project

Top PBS Levels

PBS	Task	WBS	Description
4		1	Endcap Signal Feedthroughs
4.1		2	Project Setup
4.1.1		3	Leak Test Setup
4.1.2		3	Electric Test Setup
4.1.3		3	Data Acquisition System
4.1.4		3	FT Assembly Tools
4.1.5		3	FT Prototypes
4.1.6		3	Management Tools
4.2		2	FT Series Assemblies
4.2	D	3	Design
4.2	AO	3	Assembly for ECC
4.2	T	3	Testing and Commissioning for ECC
4.2	A	3	Installation on ECC
4.2	AO	3	Assembly for ECA
4.2	T	3	Testing and Commissioning for ECA
4.2	A	3	Installation on ECA
4.2	RE	3	Repairs
4.2.1		3	Mechanical Components
4.2.1.1		4	Pin Carriers
4.2.1.2		4	Warm Flanges
4.2.1.3		4	Cold Flanges
4.2.1.4		4	Bellow Assemblies
4.2.1.5		4	Bolt Flanges
4.2.1.6		4	Funnel Assemblies
4.2.1.7		4	Pipe Fittings
4.2.2		3	Electrical Components
4.2.2.1		4	Pig Tail Cables
4.2.2.2		4	Vacuum Cables
4.2.2.3		4	Low Voltage Pigtail Cables
4.2.2.4		4	Low Voltage Vacuum Cables
4.2.2.5		4	Heaters
4.2.3		3	Shipping Crates

4.n **for ATLAS Canada corresponds to**
4.2.2.1.n **in the TDR**

Endcap Signal Feedthrough Project Installation

PBS	Task	WBS	Description	1996	1997	1998	1999	2000	2001	2002	2003
4		1	Endcap Signal Feedthroughs	[Overall Project Duration: 1996 to 2003]							
4.1		2	Project Setup	[Duration: 1996 to mid-1998]							
4.2		2	FT Series Assemblies	[Overall Duration: 1996 to 2003]							
4.2	D	3	Design	[Duration: 1996 to mid-1998]							
4.2	AO	3	Assembly for ECC	[Duration: mid-1998 to early 2000]							
4.2	T	3	Testing and Commissioning for ECC	[Duration: early 2000 to mid-2000]							
4.2	A	3	Installation on ECC	[Duration: mid-2000 to early 2001]							
4.2	AO	3	Assembly for ECA	[Duration: early 2001 to mid-2001]							
4.2	T	3	Testing and Commissioning for ECA	[Duration: mid-2001 to early 2002]							
4.2	A	3	Installation on ECA	[Duration: early 2002 to mid-2002]							
4.2	RE	3	Repairs	[Duration: mid-2002 to 2003]							
4.2.1		3	Mechanical Components	[Duration: mid-1998 to early 2001]							
4.2.2		3	Electrical Components	[Duration: mid-1998 to early 2001]							
4.2.3		3	Shipping Crates	[Duration: early 2000 to early 2001]							


Dates Assumed (CB of 11/06/98)

24/11/00 for 90 days Installation on ECC

22/02/02 for 90 days Installation on ECA

Endcap Signal Feedthrough Project


Schedule: Mechanical Components



- Pin Carriers ordered shortly after PRR
- Contract preparation to start in 1998

Endcap Signal Feedthrough Project

Schedule: Electrical Components



- Critical dates: Pigtails last delivery dates for EEC and ECA
- Currently, no contingency...

Endcap Signal Feedthrough Project

Project Setup Details

ID	PBS	Task	WBS	Description	1996				1997				1998							
					Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1			
1	4		1	Endcap Signal Feedthroughs																
2	4.1		2	Project Setup																
3	4.1.1		3	Leak Test Setup																
4	4.1.1	D	4	Design																
5	4.1.1	A	4	Assembly																
6	4.1.1	T	4	Testing and Commissioning																
7	4.1.2		3	Electric Test Setup																
8	4.1.2	D	4	Design																
9	4.1.2	T	4	Testing and Commissioning																
10	4.1.3		3	Data Acquisition System																
11	4.1.3	T	4	Testing and Commissioning																
12	4.1.4		3	FT Assembly Tools																
16	4.1.5		3	FT Prototypes																
17	4.1.5	D	4	Design																
18	4.1.5	A	4	Assembly																
19	4.1.5	T	4	Testing																
20	4.1.5.1		4	Model FT																
21	4.1.5.1	FM	5	Manufacturing																
22	4.1.5.2		4	Weld Test Flanges and Pin Carriers																
31	4.1.5.3		4	Glass Pin Carriers																
32	4.1.5.3	CO	5	Ordering																
33	4.1.5.3	CR	5	Reception																
34	4.1.5.4		4	Ceramic Pin Carriers																
35	4.1.5.4	CO	5	Ordering																
36	4.1.5.4	CR	5	Reception																
37	4.1.5.5		4	Warm Flanges																
38	4.1.5.5	CO	5	Ordering																
39	4.1.5.5	CR	5	Reception																
40	4.1.5.6		4	Cold Flanges																
43	4.1.5.6		4	Bellows Assemblies																
46	4.1.5.7		4	Bolt Flanges																
49	4.1.5.8		4	Funnel Assemblies																
52	4.1.5.9		4	Vacuum Cables																
53	4.1.5.9	D	5	Design																
54	4.1.5.9.1		5	Strip Assembly Prototypes																
57	4.1.5.9.2		5	Connector Prototypes																
60	4.1.5.9.3		5	Complete Assembly for Prototypes																
64	4.1.5.10		4	Low Voltage Vacuum cables																
69	4.1.5.11		4	Low Voltage Pigtails																
74	4.1.5.12		4	Pipe Fittings																
77	4.1.6		3	Management Tools																

Endcap Signal Feedthrough Project

- Design Finalized
- Prototypes under construction
 - pin carrier technology choice
 - no pigtails for prototypes
 - Some vacuum cables
- Vacuum cable development progressing
- Assembly and test stations near completion
- Critical path items:
 - pin carrier technology choice
 - pigtail procurement
 - vacuum cable development
- Ongoing
 - Low voltage special cables (pigtails, low voltage)
 - flange insulation issues